ROYALTY CALCULATION

Name of Work:Providing Infrastructure Programmes to SC/ST Communities in Dasarahalli Zone

014-22-000005 Est Cost. Rs. 85.00 Lakhs

Plain Cement Concrete 1:4:8			
Description	**Qty in Cum**	**Constant**	**Total Qty**
Sand	150.28	0.57	85.66
Jelly	150.28	0.85	127.74
Cement Concrete M20			
Sand	364.32	0.46	167.59
Jelly	364.32	0.69	251.38
Precast Concrete Slab 100 MM thick			
Sand	74.4	0.47	34.97
Jelly	74.4	0.70	52.08

Sl	Items	Qty		Rate		Amount
1	Sand	288.21	X	138	=	39772.98
2	Jelly	431.20	X	126	=	54331.20
					Total	94104.18

Note: Only Qty is Given By Sub Division office

Asst.Engineer
Ward No 14

Asst.Executive Engineer
T.Dasarahalli Sub Division

Assistant Executive Engineer
T. Dasarahalli Sub Division
Bagalagunte, BBMP
Bangalore-560073